SMUD Cable Fault and Transmission Line Zero Sequence Mutual Impedance Testing

Bryan Diemer

March 6, 2025, WECC Protection and Control Subcommittee WECC Offices, Salt Lake City, UT



Powering forward. Together.



- Quick review of impedance testing due to faulty cable models.
- 20kA 115kV cable fault occurred last week on February 25th.
- Overhead transmission line zero sequence mutual impedance testing results and analysis.



Downtown Sacramento 115kV Underground Cable System and 2021 Fault



115kV Network Changes Between the 2021 and 2025 Events

- Station A was built in 1895 as the terminal fed from Folsom generation, then the longest 3-phase AC transmission line in the U.S. (11 miles at 22kV). It was replaced by Station G in 2023.
 - High Pressure Oil Filled (HPOF) cables were installed in 1954.
 - New short HPOF cable sections were spliced near the Station G and Station E terminals.
- Impedance testing of the HPOF cables revealed substantial cable impedance modeling errors.
- Some 21 distance relays were revised based on the test data; others were *still* not changed.











2025 Downtown Sacramento 115kV Underground Cable System and Cable Fault





Protective Relay Response

- 20kA fault was cleared in 2 cycles by Station G GIS breakers, 2.5 cycles by Station E SF6 breakers.
- Multi-ended fault location by the 411L relays matched at both ends.
 - The 311L relays did not provide good single-ended fault locations;
 - The 411L relays did not provide travelling wave fault locations, likely due to incorrect LPLVL settings (investigation continues).
- Relay/DFR data and our updated ASPEN OneLiner model – all match within 3%. The ASPEN model is accurate.
- The Station D zone I and II elements correctly picked up.





Overhead Transmission Line Zero Sequence Mutual Coupling Impedance Testing



Omicron CPC-100 with CP CU1



Zero Sequence Mutual Coupling

With line self tests, the parallel line is grounded only at one terminal. To test for zero sequence mutual coupling, run the same line under test, but ground **both** ends of the parallel line.





Overhead Line Self-Impedance Test Results

- Positive sequence tested values match within 1-3% of calculated values, where zero sequence self-impedances are 20-35% *lower* than calculated, for two primary reasons:
 - OPGW incorrectly modeled;
 - Ground impedances (ρ, in Ω/mi) are either much lower (in the Sacramento Valley) or much higher (in the high Sierra) than assumed.



First Test: Lines terminated into the same substations



Rancho Seco



Comparison of Zero Sequence Mutual Impedance Test Results to Modeling Data

- The mutual tests were performed twice, once with line #1 under test and parallel line #2 grounded at both ends, then repeated vice versa. Results were identical, as expected.
- Good results between measured and calculated mutual coupling, after correcting for the following:
 - Ground impedance was originally 100 Ω /Meter everywhere; now using 15 Ω /Meter from substation ground testing results (in the Sacramento Valley).
 - Overhead shield wire sections leaving the station were originally modeled as ¹/₂" steel, now they are aluminum/steel OPGW;
 - Entirely new OPGW was installed over Section AB that was not previously accounted for.

Error Calculation:										
			Z ₁		Z ₀		Z _{om}		Z _{0M}	
			R / Ω	Χ/Ω	R / Ω	Χ/Ω	R/Ω	Χ / Ω	Ζ/Ω	φ / °
Tested Value / Ω:			0.82	8.48	3.93	25.71	3.08	14.72	15.04	78.18
Calculated Value / Ω:		0.85	8.47	4.25	27.15	3.26	15.19	15.55	77.70	
Error (ref. to tested value) / %:		-3.66	0.12	-8.14	-5.60	-5.84	-3.19			



Second Test: Three 69kV Lines Under Test, All Double Circuit Vertical Towers



Union Valley shooting to Loon Lake. Line in blue is the line being tested from Union Valley, with Union Valley to Robb's Peak grounded at both ends.









Robb's Peak shooting to Loon Lake. Line in blue is the line being tested (system I) with the Union Valley - Robb's Peak line grounded at both ends. Loon Union HA 6.7 Mi HC 5.6 Mi Valley Lake (LNL) (UNV) This test is trying to measure the mutual coupling on the tested line with a 1.2 mile This is section HB system II; however, the circulating ground under mutual coupling path is between UNV and ROB at 6.8 test. miles, which is ~6x the true section HC With a *much* longer circulating mutual path: path with a ground p resistance 0.676 +j 1.971 Calculated 71° increase >> than the OPGW Ω , 4.261 +j 2.744 Measured 33° reactive increase, this is why the mutual coupling measurement is HB 1.2 Mi completely shifted in angle. 6.81 Mi Test set location. н Robb's Peak (ROB)



Conclusions and Next Steps

- The grounding of the parallel line needed to be at the TEE point (Tower 39), *not* at the remote station for mutual impedance testing:
 - This is the only true mutually coupled section;
 - We will correct this procedurally going forward;
- The testing errors backed me into trusting the mutual modeling.
- Late 2025 we will test this against a new set of partially parallel lines.



Our Transmission Line Department's Maps Now Show ADSS/OPGW Installations





Bryan Diemer Principal Protection Engineer (SPAC) w. 916.732.6433 c. 916.753.5510 bryan.diemer@smud.org 6201 S Street, Mail Stop D112, Sacramento, CA 95817 P.O. Box 15830, Sacramento, CA 95852-0830

