A. Introduction

- 1. Title: Reliability Coordinator Operational Analyses and Real-time Assessments
- **2. Number:** IRO-008-3
- **3. Purpose:** Perform analyses and assessments to prevent instability, uncontrolled separation, or Cascading.
- 4. Applicability

4.1. Reliability Coordinator.

- 5. Effective Date*: See BC Implementation Plan Establish and Communicate SOLs.
- 6. Background

See Project 2014-03 project page.

B. Requirements and Measures

- **R1.** Each Reliability Coordinator shall perform an Operational Planning Analysis that will allow it to assess whether the planned operations for the next-day will exceed System Operating Limits (SOLs) and Interconnection Reliability Operating Limits (IROLs) within its Wide Area. [*Violation Risk Factor: Medium*] [*Time Horizon: Operations Planning*]
- **M1**. Each Reliability Coordinator shall have evidence of a completed Operational Planning Analysis. Such evidence could include but is not limited to dated power flow study results.
- **R2.** Each Reliability Coordinator shall have a coordinated Operating Plan(s) for next-day operations to address potential System Operating Limit (SOL) and Interconnection Reliability Operating Limit (IROL) exceedances identified as a result of its Operational Planning Analysis as performed in Requirement R1 while considering the Operating Plans for the next-day provided by its Transmission Operators and Balancing Authorities. [*Violation Risk Factor: Medium*] [*Time Horizon: Operations Planning*]
- M2. Each Reliability Coordinator shall have evidence that it has a coordinated Operating Plan for next-day operations to address potential System Operating Limit (SOL) and Interconnection Reliability Operating Limit (IROL) exceedances identified as a result of the Operational Planning Analysis performed in Requirement R1 while considering the Operating Plans for the next-day provided by its Transmission Operators and Balancing Authorities. Such evidence could include but is not limited to plans for precluding operating in excess of each SOL and IROL that were identified as a result of the Operational Planning Analysis.

- **R3.** Each Reliability Coordinator shall notify impacted entities identified in its Operating Plan(s) cited in Requirement R2 as to their role in such plan(s). [Violation Risk Factor: Medium] [Time Horizon: Operations Planning]
- M3. Each Reliability Coordinator shall have evidence that it notified impacted entities identified in its Operating Plan(s) cited in Requirement R2 as to their role in such plan(s). Such evidence could include, but is not limited to, dated operator logs, or e-mail records.
- **R4.** Each Reliability Coordinator shall ensure that a Real-time Assessment is performed at least once every 30 minutes. [Violation Risk Factor: High] [Time Horizon: Sameday Operations, Real-time Operations]
- M4. Each Reliability Coordinator shall have, and make available upon request, evidence to show it ensured that a Real-time Assessment is performed at least once every 30 minutes. This evidence could include but is not limited to dated computer logs showing times the assessment was conducted, dated checklists, or other evidence.
- **R5.** Each Reliability Coordinator shall notify, in accordance with its SOL methodology, impacted Transmission Operators and Balancing Authorities within its Reliability Coordinator Area, and other impacted Reliability Coordinators as indicated in its Operating Plan, when the results of a Real-time Assessment indicate an actual or expected condition that results in, or could result in, a System Operating Limit (SOL) exceedance or an Interconnection Reliability Operating Limit (IROL) exceedance within its Wide Area. [Violation Risk Factor: High] [Time Horizon: Same-Day Operations, Real-time Operations]
- M5. Each Reliability Coordinator shall make available upon request, evidence that it informed, in accordance with its SOL methodology impacted Transmission Operators and Balancing Authorities within its Reliability Coordinator Area, and other impacted Reliability Coordinators as indicated in its Operating Plan, of its actual or expected operations that result in, or could result in, a System Operating Limit (SOL) exceedance or an Interconnection Reliability Operating Limit (IROL) exceedance within its Wide Area. Such evidence could include but is not limited to dated operator logs, voice recordings or transcripts of voice recordings, electronic communications, or other equivalent evidence. If such a situation has not occurred, the Reliability Coordinator may provide an attestation.
- **R6.** Each Reliability Coordinator shall notify, in accordance with SOL methodology, impacted Transmission Operators and Balancing Authorities within its Reliability Coordinator Area, and other impacted Reliability Coordinators as indicated in its Operating Plan, when the System Operating Limit (SOL) exceedance or an Interconnection Reliability Operating Limit (IROL) exceedance identified in Requirement R5 has been prevented or mitigated. [Violation Risk Factor: Medium] [Time Horizon: Same-Day Operations, Real-time Operations]

- M6. Each Reliability Coordinator shall make available upon request, evidence that it informed, in accordance with its SOL methodology impacted Transmission Operators and Balancing Authorities within its Reliability Coordinator Area, and other impacted Reliability Coordinators as indicated in its Operating Plan, when the System Operating Limit (SOL) exceedance or an Interconnection Reliability Operating Limit (IROL) exceedance identified in Requirement R5 has been prevented or mitigated. Such evidence could include but is not limited to dated operator logs, voice recordings or transcripts of voice recordings, electronic communications, or other equivalent evidence. If such a situation has not occurred, the Reliability Coordinator may provide an attestation.
- **R7.** Each Reliability Coordinator shall use its SOL methodology when determining SOL exceedances for Real-time Assessments, Real-time monitoring, and Operational Planning Analysis. [Violation Risk Factor: Medium] [Time Horizon: Same-Day Operations, Real-time Operations, Operations Planning]
- M7. Each Reliability Coordinator shall have, and provide upon request, evidence that it used its SOL methodology for determining SOL exceedances for Real-time Assessments, Real-time monitoring, and Operational Planning Analysis. Evidence could include, but is not limited to: Operating Plans, contingency sets, SOLs, alarming and study reporting thresholds, operator logs, voice recordings or other equivalent evidence.

C. Compliance

1. Compliance Monitoring Process

1.1. Compliance Enforcement Authority (CEA)

The British Columbia Utilities Commission.

1.2. Data Retention

The following evidence retention periods identify the period of time an entity is required to retain specific evidence to demonstrate compliance. For instances where the evidence retention period specified below is shorter than the time since the last audit, the Compliance Enforcement Authority may ask an entity to provide other evidence to show that it was compliant for the full time period since the last audit.

Each Reliability Coordinator shall keep data or evidence to show compliance for Requirements R1 through R3, R5, R6, and R7 and Measures M1 through M3, M5, M6, and M7 for a rolling 90-calendar days period for analyses, the most recent 90-calendar days for voice recordings, and 12 months for operating logs and email records unless directed by its Compliance Enforcement Authority to retain specific evidence for a longer period of time as part of an investigation.

Each Reliability Coordinator shall each keep data or evidence for Requirement R4 and Measure M4 for a rolling 30-calendar day period, unless directed by its Compliance Enforcement Authority to retain specific evidence for a longer period of time as part of an investigation.

If a Reliability Coordinator is found non-compliant, it shall keep information related to the non-compliance until found compliant or the time period specified above, whichever is longer.

The Compliance Enforcement Authority shall keep the last audit records and all requested and submitted subsequent audit records.

1.3. Additional Compliance Information

None

Table of Compliance Elements

	Time Horizons	VRF	Violation Severity Levels				
R#			Lower VSL	Moderate VSL	High VSL	Severe VSL	
R1	Operations Planning	Medium	N/A	N/A	N/A	The Reliability Coordinator did not perform an Operational Planning Analysis allowing it to assess whether its planned operations for the next-day within its Wide Area will exceed any of its System Operating Limits (SOLs) and Interconnection Reliability Operating Limits (IROLs).	
R2	Operations Planning	Medium	N/A	N/A	N/A	The Reliability Coordinator did not have a coordinated Operating Plan(s) for next-day operations to address potential System Operating Limit (SOL) and Interconnection Reliability Operating Limit (IROL) exceedances identified as a result of its Operational Planning Analysis as performed in Requirement R1 while considering the Operating Plans for the next- day provided by its Transmission Operators and Balancing Authorities.	

			Violation Severity Levels						
R#	Time Horizons	VRF	Lower VSL	Moderate VSL	High VSL	Severe VSL			
find th	For the Requirement R3 and R5 VSLs, the intent of the SDT is to start with the Severe VSL first and then to work your way to the left until you Find the situation that fits. In this manner, the VSL will not be discriminatory by size. If a Reliability Coordinator has just one affected reliability For the inform, the intent is that that situation would be a Severe violation								
R3	Operations Planning	Medium	The Reliability Coordinator did not notify one impacted entity or 5% or less of the impacted entities whichever is greater identified in its Operating Plan(s) as to their role in that plan(s).	The Reliability Coordinator did not notify two impacted entities or more than 5% and less than or equal to 10% of the impacted entities whichever is greater, identified in its Operating Plan(s) as to their role in that plan(s).	The Reliability Coordinator did not notify three impacted entities or more than 10% and less than or equal to 15% of the impacted entities whichever is greater, identified in its Operating Plan(s) as to their role in that plan(s).	The Reliability Coordinator did not notify four or more impacted entities or more than 15% of the impacted entities identified in its Operating Plan(s) as to their role in that plan(s).			
R4	Same-day Operations, Real-time Operations	High	For any sample 24-hour period within the 30- day retention period, the Reliability	For any sample 24-hour period within the 30-day retention period, the Reliability Coordinator's	For any sample 24-hour period within the 30- day retention period, the Reliability	For any sample 24-hour period within the 30-day retention period, the Reliability Coordinator's Real-time Assessment was not conducted for three or more 30-minute periods			

Page 6 of 14

	Time Horizons	VRF	Violation Severity Levels				
R#			Lower VSL	Moderate VSL	High VSL	Severe VSL	
			Coordinator's Real-time Assessment was not conducted for one 30- minute period within that 24- hour period.	Real-time Assessment was not conducted for two 30-minute periods within that 24-hour period.	Coordinator's Real-time Assessment was not conducted for three 30- minute periods within that 24- hour period.	within that 24-hour period.	
R5	Same-Day Operations, Real-time Operations	High	The Reliability Coordinator did not notify, in accordance with its SOL methodology one impacted Transmission Operator or Balancing Authority within its Reliability Coordinator Area or 5% or less of the impacted Transmission Operators and	The Reliability Coordinator did not notify, in accordance with its SOL methodology two impacted Transmission Operators and Balancing Authorities within its Reliability Coordinator Area or more than 5% and less than or equal to 10% of the impacted Transmission	The Reliability Coordinator did not notify, in accordance with its SOL methodology three impacted Transmission Operators and Balancing Authorities within its Reliability Coordinator Area or more than 10% and less than or equal to 15% of	The Reliability Coordinator did not notify, in accordance with its SOL methodology four or more impacted Transmission Operators and Balancing Authorities within its Reliability Coordinator Area or more than 15% of the impacted Transmission Operators and Balancing Authorities within its Reliability Coordinator Area identified in the Operating Plan(s) as to their role in the plan(s). OR The Reliability Coordinator did not notify the other impacted Reliability Coordinators, as indicated in its Operating Plan,	

	Time Horizons	VRF	Violation Severity Levels				
R#			Lower VSL	Moderate VSL	High VSL	Severe VSL	
			Balancing Authorities within its Reliability Coordinator Area whichever is greater, when the results of its Real-time Assessment indicate an actual or expected condition that results in, or could result in, a System Operating Limit (SOL) exceedance or an Interconnection Reliability Operating Limit (IROL) exceedance within its Wide	Operators and Balancing Authorities within its Reliability Coordinator Area whichever is greater, when the results of its Real- time Assessment indicate an actual or expected condition that results in, or could result in, a System Operating Limit (SOL) exceedance or an Interconnection Reliability Operating Limit (IROL) exceedance within its Wide Area.	the impacted Transmission Operators and Balancing Authorities within its Reliability Coordinator Area whichever is greater, when the results of its Real-time Assessment indicate an actual or expected condition that results in, or could result in, a System Operating Limit (SOL) exceedance or an Interconnection Reliability Operating Limit	when the results of its Real-time Assessment indicate an actual or expected condition that results in, or could result in, a System Operating Limit (SOL) exceedance or an Interconnection Reliability Operating Limit (IROL) exceedance within its Wide Area.	

	Time Horizons	VRF	Violation Severity Levels				
R#			Lower VSL	Moderate VSL	High VSL	Severe VSL	
			Area.		(IROL) exceedance within its Wide Area.		
R6	Same-Day Operations, Real-time Operations	Medium	The Reliability Coordinator did not notify, in accordance with its SOL methodology one impacted Transmission Operator or Balancing Authority within its Reliability Coordinator Area or 5% or less of the impacted Transmission Operators and Balancing Authorities within its Reliability	The Reliability Coordinator did not notify, in accordance with its SOL methodology two impacted Transmission Operators or Balancing Authorities within its Reliability Coordinator Area or more than 5% and less than or equal to 10% of the impacted Transmission Operators and Balancing Authorities within its Reliability	The Reliability Coordinator did not notify, in accordance with its SOL methodology three impacted Transmission Operators or Balancing Authorities within its Reliability Coordinator Area or more than 10% and less than or equal to 15% of the impacted Transmission Operators and Balancing	The Reliability Coordinator did not notify, in accordance with its SOL methodology four or more impacted Transmission Operators or Balancing Authorities within its Reliability Coordinator Area or more than 15% of the impacted Transmission Operators and Balancing Authorities within its Reliability Coordinator Area when the System Operating Limit (SOL) exceedance or an Interconnection Reliability Operating Limit (IROL) exceedance identified in Requirement R5 was prevented or mitigated. OR The Reliability Coordinator did not notify four or more other impacted Reliability Coordinators as indicated in its Operating Plan	

	Time Horizons	VRF	Violation Severity Levels				
R#			Lower VSL	Moderate VSL	High VSL	Severe VSL	
			Coordinator Area whichever is greater, when the System Operating Limit (SOL) exceedance or an Interconnection Reliability Operating Limit (IROL) exceedance identified in Requirement R5 was prevented or mitigated. OR The Reliability Coordinator did not notify one other impacted Reliability Coordinator as indicated in its Operating Plan	Coordinator Area whichever is greater, when the System Operating Limit (SOL) exceedance or an Interconnection Reliability Operating Limit (IROL) exceedance identified in Requirement R6 was prevented or mitigated. OR The Reliability Coordinator did not notify two other impacted Reliability Coordinators as indicated in its Operating Plan when the System Operating Limit	Authorities within its Reliability Coordinator Area whichever is greater, when the System Operating Limit (SOL) exceedance or an Interconnection Reliability Operating Limit (IROL) exceedance identified in Requirement R5 was prevented or mitigated. OR The Reliability Coordinator did not notify three other impacted Reliability	when the System Operating Limit (SOL) exceedance or an Interconnection Reliability Operating Limit (IROL) exceedance identified in Requirement R5 was prevented or mitigated.	

	Time Heringer	VRF	Violation Severity Levels				
R#	Time Horizons		Lower VSL	Moderate VSL	High VSL	Severe VSL	
			when the when the System Operating Limit (SOL) exceedance or an Interconnection Reliability Operating Limit (IROL) exceedance identified in Requirement R5 was prevented or mitigated.	(SOL) exceedance or an Interconnection Reliability Operating Limit (IROL) exceedance identified in Requirement R5 was prevented or mitigated.	Coordinators as indicated in its Operating Plan when the System Operating Limit (SOL) exceedance or an Interconnection Reliability Operating Limit (IROL) exceedance identified in Requirement R5 was prevented or mitigated.		
R7	Same-Day Operations, Real-time Operations	Medium				The Reliability Coordinator failed to use its SOL methodology when determining SOL exceedances for Real-time Assessments, Real-time monitoring, and Operational Planning Analysis.	

D. Regional Variances

None

E. Interpretations

None

F. Associated Documents

Operating Plan - An Operating Plan includes general Operating Processes and specific Operating Procedures. It may be an overview document which provides a prescription for an Operating Plan for the next-day, or it may be a specific plan to address a specific SOL or IROL exceedance identified in the Operational Planning Analysis (OPA). Consistent with the NERC definition, Operating Plans can be general in nature, or they can be specific plans to address specific reliability issues. The use of the term Operating Plan in the revised TOP/IRO standards allows room for both. An Operating Plan references processes and procedures, including electronic data exchange, which are available to the System Operator on a daily basis to allow the operator to reliably address conditions which may arise throughout the day. It is valid for tomorrow, the day after, and the day after that. Operating Plans should be augmented by temporary operating guides which outline prevention/mitigation plans for specific situations which are identified day-to-day in an OPA or a Real-time Assessment (RTA). As the definition in the Glossary of Terms states, a restoration plan is an example of an Operating Plan. It contains all the overarching principles that the System Operator needs to work his/her way through the restoration process. It is not a specific document written for a specific blackout scenario but rather a collection of tools consisting of processes, procedures, and automated software systems that are available to the operator to use in restoring the system. An Operating Plan can in turn be looked upon in a similar manner. It does not contain a prescription for the specific set-up for tomorrow but contains a treatment of all the processes, procedures, and automated software systems that are at the operator's disposal. The existence of an Operating Plan, however, does not preclude the need for creating specific action plans for specific SOL or IROL exceedances identified in the OPA. When a Reliability Coordinator performs an OPA, the analysis may reveal instances of possible SOL or IROL exceedances for pre- or post-Contingency conditions. In these instances, Reliability Coordinators are expected to ensure that there are plans in place to prevent or mitigate those SOLs or IROLs, should those operating conditions be encountered the next day. The Operating Plan may contain a description of the process by which specific prevention or mitigation plans for day-to-day SOL or IROL exceedances identified in the OPA are handled and communicated. This approach could alleviate any potential administrative burden associated with perceived requirements for continual day-to-day updating of "the Operating Plan document" for compliance purposes.

ATTACHMENT D

Version History

Version	Date	Action	Change Tracking
1	October 17, 2008	Adopted by NERC Board of Trustees	
1	March 17, 2011	Order issued by FERC approving IRO- 008-1 (approval effective 5/23/11)	
1	February 28, 2014	Updated VSLs and VRF's based on June 24, 2013 approval.	
2	November 13, 2014	Adopted by NERC Board of Trustees	Revisions under Project 2014-03
2	November 19, 2015	FERC approved IRO-008-2. Docket No. RM15-16-000. Order No. 817	
3	May 13, 2021	Adopted by NERC Board of Trustees	Revisions under Project 2015-09
3	March 4, 2022	FERC approved IRO-008-3. Docket No. RD22-2-000.	
3	March 9,2022	Effective Date	April 1,2024

Note: The Guidelines and Technical Basis section has not been revised as part of Project 2015-09. A separate technical rationale document has been created to cover Project 2015-09 revisions. Future edits to this section will be conducted through the Technical Rationale for Reliability Standards Project and the Standards Drafting Process.

Page 14 of 14

British Columbia Utilities Commission

Implementation Plan – Establish and Communicate System Operating Limits Standards

Applicable Standard(s) and Definitions

- FAC-003-5 Transmission Vegetation Management
- FAC-011-4 System Operating Limits Methodology for the Operations Horizon
- FAC-014-3 Establish and Communicate System Operating Limits
- IRO-008-3 Reliability Coordinator Operational Analyses and Real-time Assessments
- PRC-002-3 Disturbance Monitoring and Reporting Requirements
- TOP-001-6 Transmission Operations
- Definition of System Voltage Limit in the Glossary of Terms Used in NERC Reliability Standards ("NERC Glossary")
- Definition of System Operating Limit in the NERC Glossary

Requested Retirement(s)

- FAC-003-4 Transmission Vegetation Management
- FAC-010-3 System Operating Limits Methodology for the Planning Horizon
- FAC-011-3 System Operating Limits Methodology for the Operations Horizon
- FAC-014-2 Establish and Communicate System Operating Limits
- IRO-008-2 Reliability Coordinator Operational Analyses and Real-time Assessments
- PRC-002-2 Disturbance Monitoring and Reporting Requirements
- TOP-001-5 Transmission Operations
- Currently effective definition of System Operating Limit

Effective Date

Reliability Standards FAC-003-5, FAC-011- 4, FAC-014-3, IRO-008-3, PRC-002-3 and TOP-001-6 and the NERC Glossary terms "System Voltage Limit" and "System Operating Limit" shall become effective the first day of the first calendar quarter that is twenty-four (24) calendar months after the effective date of the BCUC order approving the standards and terms.

Retirement Date

Currently Effective Mandatory Reliability Standards

Reliability Standards FAC-003-4, FAC-010-3, FAC-011-3, FAC-014-2, IRO-008-2, PRC-002-2 and TOP-001-5 and the current definition of System Operating Limit adopted in B.C. shall be retired immediately prior to the effective dates of the Reliability Standards FAC-003-5, FAC-011-4, FAC-014-3, IRO-008-3, PRC-002-3, TOP-001-6 and the revised definition of System Operating Limit.

Provisions for Initial Compliance

- FAC-003-5: Newly Designated Lines time period
 - A line operated below 200kV and identified in the Applicability under 4.2 becomes subject to this standard the later of: 1) 12 months after the date the Planning Coordinator, Transmission Planner or the Western Electricity Coordination Council (WECC) identified the line in Applicability under 4.2, or 2) January 1 of the planning year when the line is forecasted to be identified in Applicability under 4.2.

A line operating below 200kV identified in Applicability under 4.2 may be removed from that designation due to system improvements, changes in generation, changes in loads, or changes in studies, and analysis of the network.

- PRC-002-3 Requirements R2, R3, R4, R6, R7, R8, R9, R10, R11: Time Period to Address New Designations:
 - Entities shall be 100 percent compliant with new BES Elements identified in Requirement R1 or R5 within three (3) years following the notification by the Transmission Operator or the Reliability Coordinator.
- FAC-014-3, Requirement R6
 - Requirement R6 shall be implemented by the Planning Coordinator or Transmission Planner following the effective date of FAC-014-3 when it begins its next cycle for conducting the studies to support its Planning Assessment.
- FAC-014-3, Requirements R7 and R8
 - Each Planning Coordinator and Transmission Planner shall comply with Requirements R7 and R8 within one year of the effective date of the standard.